

ABBREVIATIONS

ADJ. ADJACENT	TEL TELEPHONE
AFF. ABOVE FINISHED FLOOR	TEMP TEMPERED
ARCH. ARCHITECT (URAL)	THK THICKNESS
ATC. ACOUSTICAL TILE CEILING	TOS TOP OF SLAB
ADMIN. ADMINISTRATION	TOW TOP OF WALL
	TYP TYPICAL
B.D. BOARD	UON UNLESS OTHERWISE NOTED
BLDG. BUILDING	UL UNDERWRITERS LABORATORY
BK. BLOCK (ING)	
B.S. BOTH SIDES	
	VB VINYL BASE
CARP. CARPET	VERT VERTICAL
C.H. CEILING HEIGHT	VIF VERIFY IN FIELD
C.L. CENTER LINE	
CLG. CEILING	
CLO. CLOSET	
CLR. CLEAR (ANCE)	
CONC. CONCRETE	W WIDE
CONST. CONSTRUCTION	W/ WITH
CONT. CONTINUOUS	W/O WITHOUT
CONTR. CONTRACTOR	WD WOOD
C.J. CONTROL JOINT	WP WATERPROOFING
C.T. CERAMIC TILE	
DIA. DIAMETER	
D.B. DOUBLE	
DIM. DIMENSION	
DIR. DIRECTION	
DN. DOWN	
DR. DOOR	
DWG. DRAWING	
EA. EACH	
ELECT. ELECTRIC (AL)	
EQ. EQUAL	
EQUIP. EQUIPMENT	
EXIST. EXISTING	
EXT. EXTERIOR	
F.O.C. FACE OF CONCRETE	
F.F. FINISHED FLOOR	
FIN. FINISH (ED)	
F.E.C. FIRE EXTINGUISHER CABINET	
F.E. FIRE EXTINGUISHER	
F.L. FLOOR (ING)	
F.O.F. FACE OF FINISH	
F.O.S. FACE OF STUDS	
FPRF. FIRE PROOF	
FT. FOOT	
FTG. FOOTING	
FURR. FURRING	
G.C. GENERAL CONTRACT (OR)	
GL. GLASS, GLAZING	
G.W.B. GYPSUM WALLBOARD	
GYP. GYPSUM	
HDW. HARDWARE	
H.M. HOLLOW METAL	
HOR. HORIZONTAL	
HR. HOUR	
HT. HEIGHT	
INFO INFORMATION	
INSUL INSULATE (D) (ION)	
INT INTERIOR	
JT JOINT	
L LONG	
LBL LABEL (ED)	
LT LIGHT	
MECH MECHANICAL	
MET METAL	
MFR MANUFACTURER	
MISC MISCELLANEOUS	
MTD MOUNTED	
N NORTH	
NIC NOT IN CONTRACT	
NO NUMBER	
NOM NOMINAL	
NTS NOT TO SCALE	
OC ON CENTER	
OFF OFFICE	
OH OVERHEAD	
OPNG OPENING	
OPP OPPOSITE	
PLAM PLASTIC LAMINATE	
PLAS PLASTER	
PNL PANEL	
PR PAIR	
PREFAB PREFABRICATED	
PT POINT	
PTN PAINT (ED)	
PTN PARTITION	
PWD PLYWOOD	
RB RADIUS	
RB RUBBER BASE	
REF REFERENCE	
REIN REINFORCE (D) (ING)	
REQ REQUIRED	
RESIL/RES RESILIENT	
REV REVISION	
RM ROOM	
SCH SCHEDULE	
SECT SECTION	
SQ SQUARE FEET	
SIM SIMILAR	
SPEC SPECIFICATION	
STD STANDARD	
STL STEEL	
STO STORAGE	
SUSP SUSPENDED	
SF SQUARE FEET	


MATERIALS LEGEND

	CONCRETE MASONRY UNIT
	BRICK
	CONCRETE
	PLYWOOD
	REGID INSULATION
	FERROUS METAL
	WOOD, FINISH
	WOOD, ROUGH
	GLASS
	ACCOUSTICAL TILE
	GYPSUM WALLBOARD
	PLASTIC LAMINATE
	PLYWOOD
	BLANKET INSULATION

SYMBOLS

	REVISION (NUMBER)		PARTITION TYPE
	DEMOLITION NOTE		ROOM/SPACE NUMBER
	EQUIPMENT/ACCESSORY NUMBER		DOOR SYMBOL
	MATERIAL NUMBER/WINDOW TYPE		DOOR NUMBER
	ELEVATION ROOM ELEVATION NUMBER DRAWING NUMBER		SECTION LINE SECTION NUMBER DRAWING NUMBER
	ALIGN WALL		CENTER LINE
	PLAN DETAIL DETAIL NUMBER DRAWING NUMBER		
	SHEET NUMBER TYPE OF DRAWING DRAWING NUMBER		
	PARTITION ON CENTER LINE OF WINDOW MULLION		
	PARTITION ON CENTER LINE OF COLUMNS		

KEY PLAN AND PROJECT DESCRIPTION



THE PROPOSED MIRACLE TEMPLE ASSEMBLY OF GOD CHURCH IS A 9,312 SQUARE FOOT BUILDING HOUSING 388 WORSHIPPERS. THE NEWLY CONSTRUCTED FACILITY IS ONE-STORY, CONCRETE SLAB ON GRADE WITH BRICK MASONRY VENEER WALLS AND SHINGLES AND BUILT-UP ROOFS. IN ADDITION TO SANCTUARY SPACE, THE FACILITY WILL ALSO INCLUDE CLASSROOMS, OFFICES, RESTROOMS AND UTILITY SUPPORT AREAS.

LIST OF DRAWINGS

ARCHITECTURAL	
A-0000	COVER SHEET
A-00	PROJECT INFORMATION LEGEND & SYMBOLS
A-1	FLOOR PLAN
A-2	ROOF PLAN
A-3	REFLECTED CEILING PLAN
A-4	BUILDING ELEVATIONS
A-5	BUILDING SECTIONS
A-6	WALL SECTIONS
A-7	TOILETROOM PLANS AND ELEVATIONS
A-8	SPIRAL STAIRCASE, BAPTISTRY POOL AND MOVABLE PARTITION DETAILS
A-9	DOOR SCHEDULE, ALUMINUM STOREFRONT AND WINDOW DETAILS
A-10	FINISH SCHEDULE, PULPIT DETAIL AND PARTITION WALLS
STRUCTURAL	
S0.1	STRUCTURAL NOTES/LOAD TABLES
S1.0	FOUNDATION PLAN
S2.0	ROOF FRAMING PLAN
S3.0	FOUNDATION DETAILS
S4.0	FRAMING DETAILS
S4.1	FRAMING DETAILS
MECHANICAL, PLUMBING AND ELECTRICAL	
M-1	NOTES, SCHEDULES, DETAILS, SYMBOLS, ABBREVIATIONS, & PART PLANS
M-2	MECHANICAL PLAN
P-1	NOTES, SCHEDULES, DETAILS, & RISER DIAGRAMS
P-2	PLUMBING PLAN
E-1	SYMBOLS, NOTES, RISER AND SCHEDULES
E-2	LIGHTING PLAN
E-3	POWER AND SIGNAL PLAN
E-4	ROOF PLAN
E-5	FIRE ALARM ANNUNCIATOR

CODE ANALYSIS

BUILDING CODE: IBC 2009
 USE GROUP: A-3, ASSEMBLY, CHURCHES

BUILDING IS FULLY SPRINKLERED (IBC 903.2.1.3) OCCUPANT LOAD GREATER THAN 300
 CONSTRUCTION TYPE: 5B, 1 STORY, 6,000 SQ. FT.
 AREA INCREASE FOR SPRINKLER SYSTEM = 300% (IBC 506.3)
 TOTAL SQUARE FOOTAGE ALLOWED = 18,000 SQ.FT. (9,303 SQ. FT. PROVIDED)
 HEIGHT LIMIT: ONE STORY
 EXTERIOR WALLS: 0 HOURS
 BEARING WALLS (INTERIOR AND EXTERIOR): 0 HOURS
 STRUCTURAL MEMBERS: 0 HOURS
 ROOF CONSTRUCTION: 0 HOURS
 EXIT ACCESS CORRIDORS: 0 HOURS (TABLE 1018.1)
 SEATING CAPACITY: 388 PEOPLE (TOTAL BUILDING POPULATION)
 EGRESS WIDTH FOR DOORS, CORRIDORS: 70 INCHES - .15 = 466 PEOPLE MAXIMUM
 SMOKE PARTITIONS PROVIDED AT CORRIDORS: 1 HOUR RATED

Date:	
Revisions:	
Consultants:	
Certification:	

Project Title:
 MIRACLE TEMPLE ASSEMBLY OF GOD
 14111 ALBERTON ROAD
 SILVER SPRING, MARYLAND 20906
 PROJECT INFORMATION, LEGEND AND SYMBOLS

Philip Aaron Lacy, Architects
 6188 Oxon Hill Road, Suite 303
 Oxon Hill, Maryland 20745
 Phone: 301-567-8223

Date: JAN. 19, 2011
 Scale: 1/4"=1'-0"
 Drawn: FCB
 Checked: PAL
 File No. MTAG_A00

Drawing No.
 A-00
 of

Copyright 2004 Philip Aaron Lacy, Architect. All rights reserved. No portion of this document may be reproduced without written permission.

Professional Certification: I hereby certify that these documents were prepared or approved by me, and that I am a duly licensed professional architect under the laws of the State of Maryland. Architectural License number 6849 with expiration date of 11/19/2011.